

CHESHAM FENCING SUPPLIES LTD

St. Leonards road, Chivery, Nr tring, Herts HP23 6LD

Tel 01296 623139

Fax 623388

All Prices + 20%. V.A.T

November 2020



Pent Corner Summer House	1.8 x 1.8m	2.1 x 2.1m	2.4 x 2.4m
SIZE WIDTH X DEPTH	6' x 6'	7' x 7'	8' x 8'
Supply Only	£1033	£1149	£1263
Erected	£1348	£1369	£1493
3" Timber Bearers	£35	£45	£50
4 Way Pointed Roof Extra	£300.00	£350.00	£400.00



Granary Summer House	1.8 x 1.8m	2.1 x 2.1m	2.4 x 2.4m
SIZE WIDTH X DEPTH	6' x 6'	7' x 7'	8' x 8'
Supply Only	£1206	£1321	£1436
Erected	£1413	£1673	£1666
3" Timber Bearers	£35	£45	£50



Pavilion Summer House			
All sizes include 3' Veranda	2.4x 2.7m	3.0 x 2.7m	3.6m x 2.7m
SIZE WIDTH X DEPTH	8'x 9'	10' x 9'	12' x 9'
Supply Only	£1378	£1466	£1758
Erected	£1551	£1815	£1942
3" Timber Bearers	£65	£75	£85
All sizes include 90cm veranda	3m x 3.3	3.6 x 3.3	4.2 x 3.3
SIZE WIDTH X DEPTH	10' x 11'	12' x 11'	14' x 11'
Supply Only	£1776	£2034	£2271
Erected	£2006	£2236	£2466
3" Timber Bearers	£95	£105	£110

Materials Used

- 38x50mm Scandinavian redwood Framing
- 16x125mm Scandinavian redwood Shiplap
- Galvanised ring shanked Nails
- Georgian doors and windows
- Antique fittings with Key lock
- Moisture barrier lining
- 20kg Green Mineral felt
- Spirit based wood preserver
(Light Brown or Red Cedar)

We Recommend erecting on **1.** a **level*** concrete base

2. 3" Treated Timber Bearers on **level*** ground (Compacted Soil, Hardcore, Gravel)

3. When erecting on slabs you will need to use 3" Bearers

Extra charges will be incurred if the building cannot be erected on the arranged day e.g. Base not **level**, No reasonable **Access** or over-grown **vegetation** etc.

PAYMENT

A deposit on ordering with the balance payable (**a.**) when the building is ready for delivery/erection.